

# BID TABULATION - NOTICE OF INTENT TO AWARD



## 11/29/2022 Notice of Intent to Award

Bid Name: Re-Bid Installation of AudioVisual Auditorium at OPD  
ProRfx ID: ITB10182200000191  
Solicitation: **ITB# OPD/220349**  
Notifications Sent: 202 Bids: 2

Buyer: Louis Joseph  
Email: [ljoseph@ocalafl.org](mailto:ljoseph@ocalafl.org)  
Buyer Phone: 352-629-8260

**Teer Engineering**

**The Integration Factory**

ITEM	DESCRIPTION	UOM	QTY	UNIT COST	EXTENDED COST	UNIT COST	EXTENDED COST
1	Projector: NEC NP-PA804UL-W-41, properly mounted to the ceiling and aligned to the screen	EA	1	\$13,560.00	\$13,560.00	\$18,333.53	\$18,333.53
2	Cameras: AVer TR311HN, installed on the ceiling in marked locations, in combination with a camera controller, AVer CL01	EA	3	\$3,856.00	\$11,568.00	\$4,343.12	\$13,029.36
3	video mixer: Roland V-8HD installed and configured in a control room adjacent to the auditorium.	EA	1	\$4,850.00	\$4,850.00	\$3,598.35	\$3,598.35
4	Audio mixer: Behringer X32 Producer installed and configured in a control room adjacent to the auditorium	EA	1	\$2,975.00	\$2,975.00	\$3,858.81	\$3,858.81
5	Streaming appliance: Tascam VSR-264 installed in a control room adjacent to the auditorium and configured to stream to OPD social media accounts	EA	1	\$2,450.00	\$2,450.00	\$3,329.46	\$3,329.46
6	HDMI matrix switcher: Shinybow SB-5688Kp, installed and configured in a control room adjacent to the auditorium.	EA	1	\$2,876.00	\$2,876.00	\$2,935.46	\$2,935.46
7	Main speakers: JBL CBT 70J-1 + 70JE-1, mounted on the front wall near the projection screen.	EA	2	\$2,625.00	\$5,250.00	\$3,040.62	\$6,081.24
8	Subwoofers: JBL Control SB2220, mounted on front wall in marked locations	EA	2	\$1,050.00	\$2,100.00	\$1,635.62	\$3,271.24
9	Microphone system: Shure BLX288/B58 and Shure BLX188/CVL, with receivers installed and configured in a control room adjacent to the auditorium. Additionally, one (1) Shure MX412S/S installed in a podium on the stage, connected to the mixer in the control room via XLR cable.	EA	3	\$2,366.67	\$7,100.00	\$1,869.08	\$5,607.24
10	Amplifiers: Crown XLI 2500, installed in a control room adjacent to the auditorium.	EA	2	\$987.50	\$1,975.00	\$1,091.56	\$2,183.12
11	DSP/Feedback suppressor: dbx DriveRack PA2 installed and configured in a control room adjacent to the auditorium.	EA	1	\$1,485.00	\$1,485.00	\$1,565.98	\$1,565.98
12	DSP/Feedback suppressor: dbx DriveRack PA2 installed and configured in a control room adjacent to the auditorium.	EA	1	\$4,510.00	\$4,510.00	\$3,995.01	\$3,995.01
13	Stage lights: ADJ PAR829 lights, installed and connected to a Chauvet DJ OBEY4 in a control room adjacent to the auditorium. Lighting scenes are to be programmed for at least three (3) use cases/scenarios.	EA	8	\$898.13	\$7,185.00	\$814.65	\$6,517.20
14	20u equipment rack: place in the control room adjacent to the auditorium	EA	1	\$620.00	\$620.00	\$2,801.71	\$2,801.71
<b>TOTAL BID AMOUNT</b>				<b>\$68,504.00</b>		<b>\$77,107.71</b>	