



TYPICAL TIE COLUMN DIAGRAM









2	TYPICAL TIE COLUMN TERMINATIO	N
	AT TIE BEAM OR BOND BEAM	3/4" = 1'-0


				BEA	M SCH	EDULE	<u> </u>	
	ELEV. TOP OF	OE	REINFORCING			STIRRUPS		
TYPE	BEAM	SIZE "b"x"d"	BOT. CONT.	TOP CONT.	MID. CONT.	SIZE	SPACING EACH END	REMARKS
B-1	10'-4"	7 5/8"x12"	2#5	2#5		#3	@5" O.C.	
B-2	10'-4"	7 5/8"x12"	2#5	2#5		#3	@5" O.C.	



TYPICAL CAST-IN-PLACE CONCRETE BEAM BAR PLACING DIAGRAM




CAST-IN-PLACE CONCRETE BEAM DETAILS



CORNERS - SINGLE CURTAIN

INTERSECTIONS - SINGLE CURTAIN



CORNERS - DOUBLE CURTAIN

INTERSECTIONS - DOUBLE CURTAIN

NOTE: ZERO DIMENSION IS USED TO INDICATE THAT THE BARS ARE INTENDED TO BE PLACED IN THE SAME PLANE



BEAM SCHEDULE NOTES

- 1. PRECAST PRESTRESSED SOFFIT BEAMS ARE DESIGNATED WITH ULTIMATE MOMENTS (FOOT-KIPS) IN COLUMN "A" AND ULTIMATE SHEARS (KIPS) IN THE "SPACING EACH END" COLUMN
- 2. IN PRECAST SOFFIT BEAMS, PLACE "B", "F" AND "G" BARS DIRECTLY ON TOP OF SOFFIT.
- 3. "C" AND "F" BARS OCCUR AT CONTINUOUS END OF BEAM. IF BOTH ENDS ARE CONTINUOUS, PLACE "C AND "F" BARS AT END OF BEAM ADJACENT TO BEAM WITH THE HIGHER MARK NUMBER. IN THE CASE OF REPETITIVE MARK NUMBERS, PLACE "C" AND "F" BARS AT SUPPORT BETWEEN IDENTICAL BEAM MARKS.
- 4. "D" BARS LAP OVER INTERIOR COLUMNS AND EXTEND TO FAR FACE OF COLUMN AND HOOK AT DISCONTINUOUS ENDS. WHERE NECESSARY, SPLICE "D" BARS AT MIDSPAN WITH A MINIMUM 48 BAR DIAMETER LAP SPLICE.
- 5. PROVIDE "E" AND "G" BARS AT BOTH ENDS OF SINGLE SPAN BEAMS.
- 6. DEVELOPMENT LENGTH NOTED FOR "F" AND "G" BARS ARE AS FOLLOW:

BAR SIZE	#5	#6	#7	#8	#9	
BAR LENGTH	3'-0"	3'-0"	3'-6"	4'-0"	4'-6"	

- 7. PLACE FIRST STIRRUP 2" FROM FACE OF SUPPORT. SPACE BALANCE OF STIRRUP TIES AS SCHEDULED. SPACES DESIGNATE NUMBER OF SPACES, NOT QUANTITY OF TIES. IN PRECAST SOFFIT BEAMS, SPECIFIED SHEAR OCCURS AT DISTANCE "d" FROM FACE OF SUPPORT. PLACE FIRST STIRRUP 2" FROM END OF SOFFIT, NEXT 4 TIES @6" O.C. (MAX.) AND BALANCE SPACED AT d/2 (MAX.)
- 8. FOR 30" AND DEEPER BEAMS, PROVIDE THE FOLLOWING INTERMEDIATE HORIZONTAL REINFORCING EVENLY SPACED BETWEEN THE INNERMOST LAYER OF TOP AND BOTTOM REINFORCING, OR TOP OF PRECAST SOFFIT. PROVIDE 36 BAR DIAMETER LAP AT SUPPORTS AND HOOK DISCONTINUOUS ENDS.

INTERMEDIATE HORIZONTAL REINFORCING									
BEAM DEPTH	30"≤ d <36"	36"≤ d <46"	46"≤ d <56"	56"≤ d <56"	66" AND GREATER				
REINF. EA. FACE	2 #5	3 #5	4 #5	5 #5	#5@10" O.C.				

- 9. FOR BARS SPECIFIED AS "CONTINUOUS", EXTEND BARS TO THE END OF THE BEAM FRAME AND HOOK, U.O.N. WHERE NECESSARY, SPLICE TOP BARS AT MIDSPAN AND BOTTOM BARS AT SUPPORTS WITH A 48 BAR DIAMETER LAP
- 10. EXTEND ALL HOOKED BARS TO FACE OF SUPPORT. WHERE NECESSARY, STAGGER ENDS OF HOOKS 2 INCHES
- 11. ALIGN BARS IN ALL LAYERS VERTICALLY AND SEPARATE MULTIPLE LAYERS OF #7 BARS AND LARGER WITH #8 SPACER BARS AT 48" O.C. BUNDLE #5 AND #6 BARS VERTICALLY.

MAXIMUM NUMBER OF BARS PER LAYER												
25242	BEAM WIDTH											
REBAR	8"	10"	12"	16"	18"	20"	24"	28"	30"	32"	36"	
#6	2	3	3	-	-	-	-	-	-	-	-	
#7	2	3	3	4	5	6	8	-	-	-	-	
#8	2	2	3	4	4	5	7	8	-	-	-	
#9	2	2	2	4	4	5	6	8	9	9	10	
#10	-	-	2	3	4	4	6	8	9	9	10	
#11	-	-	2	3	4	4	5	7	8	9	10	

BLISS & NYITR STRUCTURAL EN

BLISS & NYITRAY, INC.
STRUCTURAL ENGINEERS
FL Certificate of Authorization No. 674
www.bniengineers.com BNI Proj. No.23w21
580 Village Blvd., Suite 310
West Palm Beach, Florida 33409
Tel. (561) 623-7081

Tel. (561) 623-7081
Lazaro Alfonso, P.E. FL Reg. No. 69782
To the best of the Structural Engineer's knowledge, the Plans and Specifications comply with the applicable minimum building codes.



CLIENT DATA

Client: CITY OF OCALA 501 NE 1st Ave. Ocala, FL 34470

PROJECT DATA

Project No: 24020
Project Na: OCALA SUNTRAN
RESTROOMS & KIOSK

ARCHITECT DATA

Carbon design & architecture 263 13th Avenue South Suite 375
St. Petersburg, FL 33701
O:: 941.362.4312
W:: www.carbonAE.com


ENGINEER DATA

ISSUE + REVISION DATA

06/25/2024

No: Description:

1 BLD24-1291
Building Comments



DRAWN BY S.C

CHECKED BY L.A

S-402
ALL SCHEDULES

100% CD's Set

6/24/2024 6:12:08 PM