SUMMARY OF ROADWAY			
ITEM NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
G-01	Mobilization	LS	1
G-03	Project Sign	EA	2
G-05	Maintenance of Traffic	LS	1
G-06	Silt Fence & Sediment Control	LF	122
FDOT-104-18	Inlet Protection System	EA	6
G-09	Clearing and Grubbing - Light	SY	2,103.00
G-11	General Excavation	CY	1,043.15
G-15	Grading (Finish)	SY	782.97
G-17	Remove & Replace Unsuitable Material	CY	260.79
G-18	Stabilized subgrade & Sub-base	SY	2,423.83
G-19	Limerock 10" Base	SY	2,055.16
G-21	Removal of Existing Concrete Sidewalks and Driveways	SY	102.00
G-22	Removal of Existing Concrete Curb & Gutter	LF	185.50
G-27-2	Mill Existing Asphalt Pavement at 1" Depth	SY	1,280.32
G-27-4	Mill Existing Asphalt Pavement at 1.5" Depth	SY	2,623.82
G-32-1	SP 9.5 Asphalt Superpave	TN	399.91
G-32-2	SP 12.5 Asphalt Superpave	TN	339.10
G-52	Construction Survey	LS	1
G-53	As-Built Drawings: Survey, Roadway, & Utilities	LS	1
G-56-E-2	Concrete Curb and Gutter, Type E	LF	588
G-80	Sod, Bahia	SY	522.00
FDOT-520- 5-42	6' Type IV Concrete Traffic Separator	LF	284

SUMMARY OF POTABLE WATER			
ITEM NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
W-01	12" PVC WATER MAIN	LF	51
W-03	DIP MJ FITTINGS 12"	EA	4
W-16	12" TAP ON EXISTING 12" WATER MAIN W/VALVE & SST STEM	EA	1
W-18	DIRECTIONAL BORE 12"	LF	216

SUMMARY OF TRAFFIC CONTROL			
ITEM NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
G-34-1	Object Marker, Type 1	EA	1
G-89-111	Single Post Sign, F & I, Less than 12 Sq. ft.	AS	8
G-91	Raised Retro-Reflective Pavement Marker w/ Adhesive	EA	111
G-93-121	Temporary Traffic Stripes and Markings, Standard, White, Solid, 6" Stripe	LF	1,915
G-93-131	Temporary Solid 6" Skip Stripe 10' x 30' White (Gross)	LF	372
G-93-141	Temporary Solid 6" Skip Stripe 2' x 4' White (Gross)	LF	300
G-93-221	Temporary Traffic Stripes and Markings, Standard, Yellow, Solid, 6" Stripe	LF	1,421
G-93-224	Temporary Traffic Stripes and Markings, Standard, Yellow, Solid, 18" Stripe	LF	138
G-93-4	Temporary Traffic Stripes and Markings, Standard, White, Solid, 24" Stripe	LF	158
G-93-6	Temporary Traffic Stripes and Markings, Standard, White, Solid, 12" Stripe	LF	167
G-94-1-121	Thermoplastic Traffic Stripes and Markings, Standard, White, Solid, 6" Stripe	LF	1,915
G-94-1-131	ThermoPlastic Solid 6" Skip Stripe 10' x 30' White (Gross)	LF	372
G-94-1-141	ThermoPlastic Solid 6" Skip Stripe 2' x 4' White (Gross)	LF	300
G-94-1-221	Thermoplastic Traffic Stripes and Markings, Standard, Yellow, Solid, 6" Stripe	LF	1,421
G-94-1-224	Thermoplastic Traffic Stripes and Markings, Standard, Yellow, Solid, 18" Stripe	LF	138
G-94-4	Thermoplastic Traffic Stripes and Markings, Standard, White, Solid, 12" Stripe	LF	167
G-94-6	Thermoplastic Traffic Stripes and Markings, Standard, White, Solid, 24" Stripe	LF	158
G-95-16	Thermoplastic Pavement Message	EW	2
G-95-17	Thermoplastic Pavement Arrow	EA	15
G-96-16	Temporary Pavement Message	EW	2
G-96-17	Temporary Pavement Arrow	EA	15

THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE DIGITALLY SIGNED AND SEALED UNDER RULE 61G15-23.004, F.A.C.

R E V I S I O N S

DATE	DESCRIPTION	DATE	DESCRIPTION
12/18/24	Revised 2'-4' Quantities		
1/6/25	Revised Quantities (6" Sol. White, 6" Sol. Yellow, RPMs, & Pavement Marking Removal)		
2/12/25	Revised Quantities (SUMMARY OF POTABLE WATER)		
2/27/25	Revised Quantities (12" PVC WATER MAIN)		

ENGINEER OF RECORD

NOEL JOHN COOPER, P.E.
P.E. LICENSE NUMBER: 69534
STATE OF FLORIDA, DATED: / / .
VALID ONLY WITH EMBOSSED SEAL

PREPARED BY

OCALA City Engineer's Office

PROJECT No. 24111
PROJECT NAME: SW 46TH AVE AT SR 40 PAVEM'T. EXP.

SUMMARY OF PAY ITEMS

SHEET No. 6